

ATLAS PIXEL SYSTEM FLEX HYBRIDS

R. Boyd University of Oklahoma March 12, 1999




Outline



- CLEOIII Si3 Flex Experience
- **First Flex Hybrid Prototypes 1.0**
- Next Flex Hybrid Prototypes 1.x
- Flex Hybrids What Is Known
- Flex Hybrids What is Undetermined
- Second Flex Prototypes and Beyond
- Flex Hybrid/Module Test & Burn In

Conclusion



CLEOIII Si3 Flex Experience





- Fabrication is complete (General Electric Corporate Research and Development, Schenectady, NY)
 - ► 610 flex circuits delivered (6 designs)
 - ► Yields from 33% to 60 % by design type
 - Extrapolating to current ATLAS design -> 80% yield
- Flex wire bonding studies at Purdue and Cornell
 - ► 8 gmf typical wire bond strength
 - Only 3 failures in over 80k flex wire bonds so far (pad delamination)
 - All wire bonds are potted
 - Quality of bond can be evaluated visually

OLIFIEP

CLEOIII Si3 Flex Experience (cont.)








Smashed bond








First Flex Hybrid Prototypes 1.0

"U" buss signal layout



OUBERP

)X X




First Flex Hybrid Prototypes 1.0 (cont.)

Other features

- 51 0402 capacitors for power decoupling
- SEIA "A" tantalum capacitors for power cable filtering
- ► 14 0402 LVDS termination resistors
- 16 solder pads at one end for signal I/O
- ► 5 solder pads at opposite end for power
- Supports MCC or MCC replacement chip
- Hole for bias connection to back side of sensor under flex
- Flex overhangs sensor by 0.5 mm on each side to provide protection from shorting and arcing to high voltage bias supply
- Fabricated at CERN






U.S. ATLAS

First Flex Hybrid Prototypes 1.0 (cont.)









First Flex Hybrid Prototypes 1.0 (cont.)


Performance


- ► It works! Nothing found to date that indicates problems with the flex hybrid
- ► Maximum voltage drop in power traces approx. 100 mV
- Waveforms look good
- Yield of 28 delivered, know of two flex NOT zero defect
- Surface mount component attachment
 - Solder (LBNL, Genoa)
 - Conductive adhesive (UOK)
 - Both seem to work acceptably
- 60 mm Kapton cover layer and adhesive on 1/2 of fabricated circuits







First Flex Hybrid Prototypes 1.0 (cont.)















Next Flex Hybrid Prototypes 1.x

- Basic goals- enhance usability, performance & functionality
 Improve usability
 - ★ Add Vcal buss
 - ★ Modify sensor back side bias access
 - \star Route to allow wire bond rework
 - ★ Min. 1.5 mm between MCC pads and corresponding pads on flex hybrid
 - Improve power trace performance and enable tests with realistic power supplies and cables
 - ★ Use of space outside of bond pads for routing leaves space for wider traces
 - ★ Addition of separate sensor bias return


 \star Separate return pads for AVCC and AVDD

Basic goals (cont.)


- Make room for Optical Link
 - ★ Move 6 MCC LVDS terminating resistors to support card
 - ★ Route with "#" buss topology eliminate 4 LVDS terminating resistors (empirical tests show this should be possible, simulations in progress)








Basic goals (cont.)





- More flexibility to allow experimentation to optimize number of decoupling capacitors and their values
 - \star Increase decoupling capacitor physical size to 0603
 - * Modify tantalum capacitor pads to accept sizes down to 0603
- Include 1206 pads for Pt1000 and sensor bias decoupling capacitor
- Add ground plane under MCC
- Provide sighting holes through flex for fiducial markers on sensor
- Add multiple vias for power busses

OUTERP



- Still designed for board supported module
- Explore cover layer options with vendors
 - ★ Strenthens Flex Hybrid, protects traces
 - ★ Provides barrier for solder and conductive adhesive to nearby traces
 - 12 mm thickness top and bottom
 - Patterned bottom cover layer (hole for sensor bias pad on bottom)
 - Top pattern must be placed with ± 50 mm accuracy





Fabrication possibilities

- **CERN**
- General Electric Corporate Research and Development (NY)

Dyconex (Zurich) - D0 experience

R & D Circuits (NJ)

- ★In house testing deliver fully functional parts only
- ★ Can do component mounting?
- ★ Meets component side cover layer specs
- ★Dual Au plating thickness' to optimize solder and bond pads
- ★ High purity Au plating -> 15 gmf wire bond pull strength
- ★In house laser cutting (die cutting?)

OUFIEP

Flex Hybrids - What Is Understood




- "U" buss layout topology works well, but consumes too much space
- Preliminary tests indicate that change to "H" buss topology will not have an adverse affect on signal quality
- Design can be fabricated with less dense routing than CLEOIII required -> more vendors, lower cost
- Consistent, successful wire bonding to flex is possible
- Construction of working Flex Hybrid Modules is possible




U.S. ATLAS

Flex Hybrids - What is Undetermined

- Final size of first prototype Optical Link (Summer 99)
- Size of second generation MCC (late 99)
- Optimal decoupling strategy/power supply interface
 - Electronics, especially FE-D (probably 1.x)
 - Full length power cable (1.x)
 - Realistic power supply (?)
- Radiation studies (waiting at LBNL)
 - Conductive adhesive
 - ► Passive components
 - ► Thermaphase
 - Coverlay materials (e.g., Pyralux)




Flex Hybrids - What is Undetermined




Mechanical studies - expansion and contraction on module (1999)

- Effects of humidity
- Thermal properties



Second Flex Prototypes and Beyond

- Prototype 2.0
 - **Should not require board support**
 - Actual size
 Optical link communication
 Power cable configuration
 Second generation MCC support
- For prototype 2.x add:
 - ▶ Refinements from 2.0 experience
 - ► Support for second generation Optical Link & MCC
- Prototype 3.0 (preproduction)
 - Final positions for "tall" components (MCC, Optical Link)
 - Support for final electronics and Optical Link
 - Decoupling requirements finalized




Flex Hybrid/Module Test & Burn In



Have identified 4 vendors who (claim they can*) test Flex Hybrids

- Microcontact (Berne) tested first prototypes before NI/AU plating step
- ► Zero Defects (CA)*
- Printed Circuit Technology (CA)*
- ► R & D Circuits (NJ)*
- Working with Albany to develop testing program for verification/QA of vendor testing
 - ► Have completed (successfully) testing of CLEOIII flex
 - Began testing 1.0 this month







Have set up and been using PixelDAQ test system at UOK since **Oct.** 98

- **★** Windows NT PC
- **The VXI crate**
- **★** GPIB interface
- \star PLL (LBNL) and PCC (Seigen)
- Langston lacks only PLL
- Albany needs PLL and PCC

Module test, burn in and QA system design to begin after prototype 1.x design








R. Boyd U.S. ATLAS Internal Review, March 99

Conclusion



- First Flex Hybrid prototypes successful
- Design requirements within capabilities of more vendors their numbers should continue to increase, costs going down
- Prototype 1.x design underway
- Reliable wire bonding to flex is possible
- Flex Hybrids appear to be an appropriate solution to module hybridization

