



# ATLAS PIXEL DETECTOR FLEX HYBRIDS

The University of Oklahoma

R. Boyd


8 November, 2001






# Contents

- Function
- Specifications
- Flex Vendors
- Prototypes
- Flex Hybrid Simulations
- Assembly
- Components
- Production
- Flex Vendors
- Flex Hybrid Test
- Schedule
- FY'02 Activities at UOK
- FY'02 Activities at Albany
- Production Schedule
- Cost




# Function

- Provide connection for:
  - ▶ Power
  - ▶ Clock
  - ▶ Data In
  - ▶ Data Out
- Between module and:
  - ▶ Power supply
  - ▶ Optical link
  - ▶ Interlock (temp. sensor)



\* Read Out Driver


# Function (continued)




Early Flex Hybrid module concept  
Optical link no longer included on module

# Function (continued)


- The Flex Hybrid provides interconnection between the 16 FE's (Front End chips) and the MCC (Module Control Chip)






# Specifications

- Pixel detector specifications:
  - ▶ Power: Current spec calls for no greater than 50 mV drop round trip for any power + return trace on Flex Hybrid
  - ▶ 150  $\mu\text{m}$  pitch on FE/MCC wire bond pads  $\rightarrow$  75  $\mu\text{m}$  traces/spaces and only 50  $\mu\text{m}$  between bond pads
  - ▶ Design must accommodate 700 V sensor bias
  - ▶ Barrel module envelope constrains component heights in some areas of flex to no greater than 0.6 mm
  - ▶ 0402 0.1  $\mu\text{F}$  capacitors are spec.'d at 0.5 mm  $\pm$  0.1 mm






# Specifications (*continued*)


## ■ Flex fabrication specifications

- ▶ Delivered size 86.6 mm x 19.6 mm
- ▶ Substrate of 25.4  $\mu\text{m}$  polyimide (Kapton or Upilex)
- ▶ Two metal layers connected by through-hole vias with no break out of via cover pads
- ▶ Sputtered seed metal (Cr or Ti) on polyimide
- ▶ 16  $\mu\text{m}$  (min.) Cu, 1  $\mu\text{m}$  - 2  $\mu\text{m}$  Ni, 0.1  $\mu\text{m}$  - 0.2  $\mu\text{m}$  Au compatible with Al ultrasonic wire bonding
- ▶ Patterned cover layers top and bottom of 25.4  $\mu\text{m}$  Pyralux with placement accuracy of  $\pm 125 \mu\text{m}$  (trying other substrates/cover layers in v3 & v4)




# Prototypes

- v1.0 Flex Hybrids: Work - two "working" modules built (bumping issues)
- v1.x: 4 Flex Hybrid modules constructed show that v1.x works
- v2.x: CERN delivered 100, Compunetics delivered 41
  - ▶ Test coupons good on electrically good flex
    - Indicates via resistance of  $\sim 10 \text{ m}\Omega$
    - Tests of trace resistances consistent with calculated and simulated values for actual thickness of Cu
    - Compunetics Cu thickness was low  $\sim 8 \mu\text{m}$
  - ▶ Some variability of wire bonding results on v2.1 (Compunetics)
    - Bond pad lift off on electrically bad flex (show evidence of over etching)
    - Results good on good flex when cleaned first
    - Learned that wire bonding is more reliable when there is no adhesive under bond pads, then:
      - Seeing average 9 gf pull strength at OU and LBL
- Both vendors have been slow to produce prototype
- Several modules have shown that v2.x works




## Prototypes (continued)

- V3 should ship - *in test, ship by Monday, latest*
  - ▶ Compunetics only - 50 good circuits, about 100 bad from first failed batch
  - ▶ Delayed by issues with plating - as with v2.1, Au plating shorted many wire bond pads, flying probe tester broken (again)
  - ▶ Still don't have 16  $\mu\text{m}$  Cu - too much being etched away by plating process
  - ▶ Supports AMS MCC and FE-I
    - In case MCC-I is not available
    - Still violates envelope (too many components and large MCC)
    - Barrel and disk pigtailed use same bond pads on flex, got rid of tab and connector of v2.x
    - Now use frame PCB as carrier and interconnect for tests of flex hybrid
- V4 is 95% same as v3
  - ▶ Supports FE-I and MCC-I
  - ▶ Delete resistors needed to interface AMS MCC with FE-I
  - ▶ Delete extra 3.5 Vdc power and extra capacitors required by AMS MCC
  - ▶ Uses same frame PCB, pigtailed as v3




# Flex Hybrid Simulations

- We've been using Maxwell Spicelink to model and simulate various aspects of the flex hybrid since we began our involvement with ATLAS
- We have developed a lot of confidence in the program
- Simulations of DSM electronics with the present bussed layout have caused concern




# Flex Hybrid Simulations (*continued*)

The weakness here is that we don't know what the input current slew rate for DSM really is, but it could be as high as 1 A/ns




Schematic of a single FE VDD and DGND bond pad connected to buss, with LDC, 2 Vdc power in and current sink driven at 250 mA/ns to simulate FE-I

# Flex Hybrid Simulations (*continued*)




Plot of simulated model and 250 mA/ns slew rate input current to FE. Blue is the voltage across the FE, without including the wire bond.




## Flex Hybrid Simulations (*continued*)

- The solution is VDD power & ground planes
  - ▶ Reduces resistance linearly
  - ▶ Reduces inductance in proportion to  $\ln(4l/2(t+w))$  - with a power plane,  $w \gg l$  between local decoupling capacitor and bond pads, so inductance "disappears"
- Plan to test this (important as backup, too!) with v4
  - ▶ Holes will be laser cut through some v4 flex where connections (bond pads, LDC's) are made to VDD/VDD\_ret
  - ▶ No electrical connection between v4 and power plane flex (inexpensive)
  - ▶ ~~Toughest part is aligning two flex and gluing them together with  $\leq 2$  mil error over flex hybrid~~
  - ▶ LDC's are mounted on power plane flex and thus do not violate envelope
  - ▶ Believe VDDA (analog) LDC's are not required - FE PSRR high
- Trying to simulate power planes - extraction takes several days




# Assembly

- Assembly of v1.0 and most of v1.x & v2.x done in labs
- About 20 flex of v1.x & v2.x have been assembled at AMA (CA), Flex One (CA) and Surface Mount Depot (OKC)
  - ▶ All efforts involved at least some degree of manual assembly
  - ▶ None used automated pick and place
  - ▶ Demonstrated need for improvements in layout and cover layer application to prevent solder leaching onto wire bond pads
- 15 v2.2 assembled at Mipot (Italy)
  - ▶ Automated pick and place
  - ▶ MCC attached and wire bonded
  - ▶ 7 passed electrical tests, various problems, not all assembly related
- On v3 there are:
  - ▶ 35 0402 capacitors
  - ▶ 4 1206 capacitors (1 HV)
  - ▶ 13 0402 resistors
  - ▶ 1 0603 NTC temperature sensor
  - ▶ 1 MCC



# Assembly (*continued*)

- V4.x will have:
  - ▶ 35 0402 capacitors (17 for power plane trials)
  - ▶ 3 1206 capacitors (1 HV)
  - ▶ 10 0402 resistors
  - ▶ 1 0603 NTC temperature sensor
  - ▶ 1 MCC
- Use of frame PCB will enable easier auto pick and place assembly
  - ▶ Flex is stabilized
  - ▶ Can easily design carrier to process more than 1 flex at a time
- SMD in OKC is working on proposal to attach flex to frame PCB and do assembly for v3 and v4
  - ▶ *Compunetics is looking at doing this for v4 - say it will help them out during test*
- Since they are local, we can be present during first assembly runs to assist and supervise




# Components

## ■ NTC

- ▶ Selected, irradiated, qualified by Wuppertal
- ▶ 4000 ordered and on hand (Wuppertal)

## ■ Irradiation


- ▶ Irradiation at CERN June, 2000, to full fluence  $1.9 \times 10^{15}$  p/cm<sup>2</sup> (24 Gev) of resistors, ceramic capacitors and flex, <sup>60</sup>Co to 60 Mrad and capacitors again at 3.5 Vdc in October, 2000
  - Capacitors show no catastrophic failure (large value changes, shorts)
  - Observe < 20% reduction of pre-irradiation value, no change in leakage
  - Have not observed any change in resistors or flex (other than color)
- ▶ HV caps irradiated with 700 V to full fluence in May, 2001
  - Observe < 20% reduction of pre-irradiation value, no change in leakage
  - Increase of leakage from less than 1 nA to about 3 nA
  - Continuing to monitor irradiated devices and controls



# Production

## ■ Deliverables

- ▶ Layout of prototype and final designs
- ▶ Simulations of flex hybrid power traces and decoupling
- ▶ Flex Hybrid test design
- ▶ 100% Flex Hybrids
- ▶ Attachment & wire bonding of (50% of?) MCC's
- ▶ Testing of (50% of?) Flex Hybrids in UOK & Albany



# Production (*continued*)

## ■ Flex fabrication


- ▶ Compunetics - 200 flex/week after "ramp up"
  - Typical of other commercial vendors
- ▶ CERN - 200 flex/mo. - if they can still do it and fix problems

## ■ Assembly of components onto Flex Hybrids

- ▶ Entire production can be done in less than one week with automated pick & place (including part tolerance verification)
- ▶ Attachment and wire bonding of MCC (UOK) - estimate 16/day = complete production of 3 hit system in 1 year

## ■ Flex testing, same rate, should be able to complete in one year


## ■ Should be much more certain of this by this time next year



# Flex Vendors


## ■ CERN PCB facility

- ▶ Charge for materials only, but:
  - Two tests required (outside vendor):
    - Before defect repair
    - After Ni/Au plating
  - More expensive/risky shipping (to US)
  - Cutting (singulation) not provided
- ▶ In house electroless Ni and Au plating
- ▶ Has fabricated v1.0, v1.1, v1.1, v1.4 and v2.2 flex
- ▶ Although functional, have never produced flex to specs (mainly material thicknesses)
- ▶ Not willing to fab more flex until 2002 - turnover in personnel
- ▶ Second batch of v2.2 of very poor quality
  - Nearly all have defects in cover layer
  - Many defects in metal
- ▶ Quoted ~\$85/flex (adding test and singulation) in 2000 - must check if they are still able/willing to fab for Pixel production



# Flex Vendors (*continued*)

- **Compunetics (Monroeville, PA)**
  - ▶ Quotes \$85/flex for production
  - ▶ In house testing (two tests, also)
  - ▶ In house laser cutting
  - ▶ Has produced v1.1, v2.1 and (producing) v3 flex
  - ▶ Out-sourced Ni and Au plating (has been source of some problems)
    - First batches of v2.1 & v3 ruined by plater
    - Continues to have problems meeting Cu thickness spec of 16 microns because of plater
  - ▶ Has produced flex for D0
- Many other potential vendors have been contacted, those that have technology tend to not be interested in small orders (< 100k units), most that will do small orders don't have technology



# Flex Vendors (*continued*)

## ■ Dyconex (Switzerland)


- ▶ ~\$10k for 50 - 100 (??) v4
- ▶ Quote \$16/flex for 4000 flex (have had similar quotes from other vendors that did not hold up)
- ▶ New materials, but have been used in HEP experiments
- ▶ Partnership with Nextek (assembly firm) - deliver assembled flex
- ▶ Great reputation, but has had limited technology in past

## ■ Speedy Circuits (Huntington Beach, CA)


- ▶ Quotes \$85/flex for 100 pieces
- ▶ Has built flex for FNAL experiments
- ▶ No in house test


## ■ Microconnex (Snoqualmie, WA)

- ▶ Quotes \$123/flex for 100 pieces
- ▶ No in house test




# Flex Hybrid Test Flow Chart v1.4






# Flex Hybrid Test Block Diagram v1.3




Genoa has a test system, but not practical to replicate most of it, nor necessary




# FY'02 Activities at UOK

- Intermediate design review completed in 2001
  - ▶ Flex Hybrid Task Force created partly as a result
    - Addresses interface, coordination issues relating to flex hybrid modules
    - Consists of R. Boyd, M. Garcia-Siveres, G. Darbo (Genoa)
    - Meet biweekly by various means
- Prepare for PRR in June (??) - basically all the following + documentation
- Complete design and fabrication of v4 (in progress)
- Complete final flex hybrid design (after FE-I module results are known - in serious jeopardy because of electronics delay)
- Specify Flex Hybrid Production Database (needs to be ready for v3 and v4)
- Graduate student doing flex modeling and sims leaves end of Dec.
- Expand clean room (searching for funding)




# FY'02 Activities at UOK (*continued*)


- Integrate new equipment into production, test (MRI grant, waiting for the check)
  - ▶ Westbond 2400 wire bonder (could take 8 weeks ARO)
    - Fully automated
    - Optical pattern recognition (tested with dummy module)
  - ▶ Plamsa cleaner
  - ▶ Optical comparator for checking envelope compliance of assembled flex hybrids
  - ▶ Environmental chamber for module burn-in
  - ▶ Logic analyzer for module debug
- Complete development of test systems
  - ▶ Design and fabricate probe card(s) (just need to get PO done)
  - ▶ Design and fabricate FE-B and FE-I load cards (after v4 design)
  - ▶ Design and fabricate new mini-support cards for AMS MCC and MCC-I (after v4 design)
- Test a lot of flex with the above (using a single 2.1 flex for now)



# FY'02 Activities at Albany

- Continue HV test system development
  - ▶ Only a few v2.2 flex left to test
  - ▶ Integrate HV test with new frame PCB paradigm
- Replicate UOK probe card-PixelDAQ assembled flex test system
  - ▶ F. Wappler and R. Bula coming to UOK for PixelDAQ training 11-19






# Production Schedule

Hard to imagine keeping this production schedule with delay in FE-I module production - need three months after module evaluation is complete to complete final design

Not likely to have a final design by then


No longer makes sense

196	1.1.1.4.1	Flex Hybrid FDR	15-Dec-00
199		Release Flex Bids	24-Apr-02
200		Flex Bid Evaluation Complete	5-Jun-02
201		Flex Hybrid PRR	3-Jul-02
202		ATLAS PM Approval of Flex Proc	17-Jul-02
203		Release initial MC for flex hybrid and assembly	17-Jul-02
204		Award Flex Contracts	31-Jul-02
218	1.1.1.4.2	Initial Flex 3.x tests complete	13-Dec-01
226	1.1.1.4.3	Start initial production buy of components	13-Dec-01
228		First outer flex delivered	20-Nov-02
230		First outer flex available for module assembly	12-Feb-03
231		Need date for first outer flex	20-Nov-03
232		Outer flex testing complete	5-Nov-03
234		First B-Layer flex delivered	5-Nov-03
235		First B-Layer flex available for modules	28-Jan-04
236		Need date for first B-layer flex	15-Jul-04
237		B-Layer flex testing complete	17-Dec-03



## Production Schedule (*continued*)

- PRR in the summer doesn't look likely
  - ▶ Probably won't have had time to test, debug, analyze, irradiate, test, analyze....
  - ▶ Also not likely to have settled on required components until above is complete, delaying initial buy date
  - ▶ Is there any difference between B layer and other flex hybrids?
- Does delaying start of flex production till FY'03 help with FY'02 budget? Does it hurt funding? (Keep in mind that the UOK funding year start April 1)



## Production Schedule (*continued*)

- Entire flex hybrid production and testing likely to be complete within 1 year of order placement
  - ▶ Biggest delays with flex hybrid prototypes has been
    - Redesign after "final" version has been released for approval
    - Low numbers of flex being built, making it necessary for vendors to "re-climb" the learning curve for these very aggressive designs
  - ▶ Flex hybrid assembly could easily be finished within 160 days after production go ahead, provided we don't use CERN
- This could free up considerable resources at the time module assembly production is beginning
- Once final flex hybrid design is in production, 1 FTE EE at OU is free from all but supervision

**MANPOWER ESTIMATE SUMMARY IN FTEs**

WBSNo: 1.1.1.4

Funding Type: Project

11/2/01 10:13:33 AM

Description: Flex Hybrids/Optical Hybrids

Institutions: All

Funding Source : All

												<i>Calcu-</i>	<i>Entered</i>
<b>PROFESSIONAL</b>	<i>FY 96</i>	<i>FY 97</i>	<i>FY 98</i>	<i>FY 99</i>	<i>FY 00</i>	<i>FY 01</i>	<i>FY 02</i>	<i>FY 03</i>	<i>FY 04</i>	<i>FY 05</i>	<i>lated</i>	<i>Entered</i>	
	<i>FY 96</i>												
											<i>Total</i>		
Software Prof.											.0	.0	
Engineer - EE											.0	.0	
Engineer - ME											.0	.0	
<b>TECHNICAL</b>													
Design & Draft								.3			.3	.0	
Electrical Technician							.3	.8	.1		1.2	.0	
Mechanical Technician											.0	.0	
Admin. Supervisor											.0	.0	
Other Admin.											.0	.0	
<b>TRADES</b>													
Contract Labor							.1	.0			.1	.0	
Shops							.0				.0	.0	
Technical Services											.0	.0	
Student					.0	2.2	1.2	.0			3.4	.0	
<b>TOTAL LABOR</b>	.0	.0	.0	.0	.0	.0	2.6	2.3	.1	.0	<b>5.0</b>	<b>.0</b>	

Trades Legend:  
 Contract Labor = Job Shopper  
 Shops = Fabrication (in-house facility) from raw materials  
 Technical Services = Rigging, electricans, etc.

**MANPOWER ESTIMATE SUMMARY IN FTEs**

WBSNo: 1.1.1.4

Funding Type: Base

11/2/01 10:11:37 AM

Description: Flex Hybrids/Optical Hybrids

Institutions: All

Funding Source : All

												<i>Calcu-</i>	<i>Entered</i>
<b>PROFESSIONAL</b>	<i>FY 96</i>	<i>FY 97</i>	<i>FY 98</i>	<i>FY 99</i>	<i>FY 00</i>	<i>FY 01</i>	<i>FY 02</i>	<i>FY 03</i>	<i>FY 04</i>	<i>FY 05</i>	<i>lated</i>	<i>Entered</i>	
	<i>FY 96</i>												
												<i>Total</i>	
Software Prof.												.0	.0
Engineer - EE												.0	.0
Engineer - ME												.0	.0
<b>TECHNICAL</b>													
Design & Draft							.3	.2				.5	.0
Electrical Technician												.0	.0
Mechanical Technician												.0	.0
Admin. Supervisor												.0	.0
Other Admin.												.0	.0
<b>TRADES</b>													
Contract Labor												.0	.0
Shops												.0	.0
Technical Services												.0	.0
Student												.0	.0
<b>TOTAL LABOR</b>	.0	.0	.0	.0	.0	.0	.3	.2	.0	.0		.5	.0

Trades Legend:  
 Contract Labor = Job Shopper  
 Shops = Fabrication (in-house facility) from raw materials  
 Technical Services = Rigging, electricans, etc.

**MANPOWER ESTIMATE SUMMARY IN FTEs**

WBSNo: 1.1.1.4

Funding Type: Project

11/2/01 10:36:27 AM

Description: Flex Hybrids/Optical Hybrids

Institutions: U. of Oklahoma

Funding Source : All

												<i>Calcu-</i>	<i>Entered</i>
												<i>lated</i>	<i>Entered</i>
<b>PROFESSIONAL</b>	<i>FY 96</i>	<i>FY 97</i>	<i>FY 98</i>	<i>FY 99</i>	<i>FY 00</i>	<i>FY 01</i>	<i>FY 02</i>	<i>FY 03</i>	<i>FY 04</i>	<i>FY 05</i>			
	<i>FY 96</i>												
												<i>Total</i>	
Software Prof.												.0	.0
Engineer - EE												.0	.0
Engineer - ME												.0	.0
<b>TECHNICAL</b>													
Design & Draft												.0	.0
Electrical Technician							.3	.3				.5	.0
Mechanical Technician												.0	.0
Admin. Supervisor												.0	.0
Other Admin.												.0	.0
<b>TRADES</b>													
Contract Labor												.0	.0
Shops												.0	.0
Technical Services												.0	.0
Student							2.0	.6				2.6	.0
<b>TOTAL LABOR</b>	.0	.0	.0	.0	.0	.0	2.2	.9	.0	.0		3.2	.0

Trades Legend:  
 Contract Labor = Job Shopper  
 Shops = Fabrication (in-house facility) from raw materials  
 Technical Services = Rigging, electricans, etc.